

LOFTWALL, INC. ACOUSTICAL PERFORMANCE TEST REPORT

SCOPE OF WORK

ASTM C423 SOUND ABSORPTION TESTING ON HEDGE, FULL AND LOW HEIGHT STORAGE UNITS

REPORT NUMBER

R4359.01-113-11-R0

TEST DATE

05/30/24

ISSUE DATE


06/05/24

PAGES

10

DOCUMENT CONTROL NUMBER

RT-R-AMER-Test-2755 (10/11/23) © 2017 INTERTEK





Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

TEST REPORT FOR LOFTWALL, INC.

Report No.: R4359.01-113-11-R0

Date: 06/05/24

REPORT ISSUED TO

LOFTWALL, INC.

2617 North Great Southwest Parkway, Suite 100 Grand Prairie, Texas 75050

SECTION 1

SCOPE

Architectural Testing, Inc. (an Intertek company) dba Intertek Building & Construction (B&C) was contracted by LOFTwall, Inc. to perform a sound absorption test. Results obtained are tested values and were secured by using the designated test methods. The complete test data is included herein. The client provided the test specimen. All measurements were conducted in the HT test chambers at Intertek B&C located in York, Pennsylvania.

This report does not constitute certification of this product nor an opinion or endorsement by this laboratory. Intertek B&C will service this report for the entire test record retention period. The test record retention period ends four years after the test date. Test records, such as detailed drawings, datasheets, representative samples of test specimens, or other pertinent project documentation, will be retained for the entire test record retention period.

Unless differently required, Intertek reports apply the "Simple Acceptance" rule, also called "Shared Risk approach" of ILAC-G8:09/2019, Guidelines on Decision Rules and Statements of Conformity.

For INTERTEK B&C:

Zachary P. Golden Kurt A. Golden **COMPLETED BY: REVIEWED BY:** Technician Team Leader Manager **Acoustical Testing** TITLE: **Acoustical Testing** TITLE: **SIGNATURE: SIGNATURE:** 06/05/24 06/05/24 DATE: DATE:

ZPG:jmcs

This report is for the exclusive use of Intertek's Client and is provided pursuant to the agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this report. Only the Client is authorized to permit copying or distribution of this report and then only in its entirety. Any use of the Intertek name or one of its marks for the sale or advertisement of the tested material, product or service must first be approved in writing by Intertek. The observations and test results in this report are relevant only to the sample(s) tested. This report by itself does not imply that the material, product, or service is or has ever been under an Intertek certification program.





Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

TEST REPORT FOR LOFTWALL, INC.

Report No.: R4359.01-113-11-R0

Date: 06/05/24

SECTION 2

SUMMARY OF TEST RESULTS

SERIES/MODEL		Hedge						
SAMPLE TYP	E	Full and Low Height Storage Units						
MOUNTING	TYPE	Type JV Mod 00						
DATA FILE		ORPHON/ ME AT THE OCTAVE BAND FREQUENCIES				Array		
NO.	125	250	500	1000	2000	4000	-NRC	-SAA
R4359.01D	0.16	0.51	0.41	0.58	0.86	1.04	0.60	0.58

SECTION 3

TEST METHODS

The specimens were evaluated in accordance with the following:

ASTM C423-23, Standard Test Method for Sound Absorption and Sound Absorption Coefficients by the Reverberation Room Method

ASTM E795-23, Standard Practices for Mounting Test Specimens During Sound Absorption Tests

SECTION 4

SPECIMEN MOUNTING

For the Type J Array mounting, the test panels were standing vertically directly against the floor of the reverberation room. The panels were arranged in one row of two with 0.76 m (30") between each row and 1.52 m (60") between each panel edge.



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

TEST REPORT FOR LOFTWALL, INC.

Report No.: R4359.01-113-11-R0

Date: 06/05/24

SECTION 5

EQUIPMENT

The equipment listed below meets the requirements of the test methods stated in Section 3 of this report.

INSTRUMENT	MANUFACTURER	MODEL	DESCRIPTION	ASSET#	CAL DATE
Data Acquisition Card	National Instruments	NI-9250	Data Acquisition Card	INT02575	06/23
Data Acquisition Card	National Instruments	NI-9250	Data Acquisition Card	INT02576	06/23
Data Acquisition Card	National Instruments	NI-9250	Data Acquisition Card	INT02577	06/23
Receive Room Microphone	PBC Piezotronics	378C20	Microphone and Preamplifier	INT03739	11/23
Receive Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	INT03720	10/23
Receive Room Microphone	PCB Piezotronics	378C20	Microphone and Preamplifier	INT02427	03/24
Receive Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	65617	07/23
Receive Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	63745	07/23
Receive Room Environmental Indicator	Comet	T7510	Receive Room	64915	02/24
Microphone Calibrator	Norsonic	1251	Acoustical Calibrator	INT03566	06/23

st-Note: The calibration frequency for this equipment is every two years per the manufacturer's recommendation.

TEST CHAMBER

	VOLUME	DESCRIPTION
RECEIVE ROOM	234 m³	Rotating vane and stationary diffusers
		Temperature and humidity controlled
		Isolation pads under the floor

SECTION 6

LIST OF OFFICIAL OBSERVERS

NAME	COMPANY
Zachary P. Golden	Intertek B&C



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

TEST REPORT FOR LOFTWALL, INC.

Report No.: R4359.01-113-11-R0

Date: 06/05/24

SECTION 7

TEST PROCEDURE

The sensitivity of the microphones was checked before measurements were conducted. Empty room sound absorption measurements were conducted before the specimen was installed. Full room sound absorption measurements were conducted after the specimen was installed.

For the empty and full room measurements, ten decay measurements were conducted at each of the five microphone positions. Data was obtained at 1/3 octave band frequencies ranging from 80 to 5000 hertz. The air temperature and relative humidity conditions were monitored and recorded during the measurements.

The specimen was returned per the client's request.

SECTION 8

TEST CALCULATIONS

The Sound Absorption Coefficient is the full room absorption minus the empty room absorption divided by the area of the sample in m². The Sound Absorption Coefficient is dimensionless.

The Noise Reduction Coefficient (NRC) rating is the arithmetic average of the sound absorption coefficients at 250, 500, 1000 and 2000 hertz. The average is rounded to the nearest multiple of 0.05.

The Sound Absorption Average (SAA) rating is the arithmetic average of the sound absorption coefficients at the frequencies ranging from 200 to 2500 hertz. The average is rounded to the nearest multiple of 0.01.

Sound absorption per M² (SA/ M²), and therefore the reported Single Number Ratings, are highly dependent on the exact sample shape, size, spacing, and extended continuous surface area present in the test and subsequent calculations. Changes to any of these parameters will change the resulting values. These presented results are valid only for the specific configuration present in the test.



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

TEST REPORT FOR LOFTWALL, INC.

Report No.: R4359.01-113-11-R0

Date: 06/05/24

SECTION 9

TEST SPECIMEN DESCRIPTION

SERIES/MODEL	Hedge
SAMPLE TYPE	Full and Low Height Storage Units
MOUNTING TYPE	Type JV Mod 00

STORAGE UNIT DESCRIPTION

The full height storage unit was 1.22 m (48") wide by 1.72 m (68") tall by 0.46 m (18") deep. The total weight of the specimen was 81.65 kg (180 lbs).

The low height storage unit was 1.22 m (48") wide by 0.89 m (35") tall by 0.46 m (18") deep. The total weight of the specimen was 49.44 kg (109 lbs).

Both panels were standing vertically on their edges as described in Section 4. The area used for the Type JV Mod 00 test specimens was 2.44 m by 2.74 m (96" by 108").

DESCRIPTION	THICKNESS	DENSITY	WEIGHT
Hodgo DET Folt	18.80 mm	217.55 kg/m ³	4.09 kg/m ²
Hedge, PET Felt	0.74"	13.46 lbs/ft ³	0.83 lbs/ft ²

Photographs are included in Section 11.

The client did not supply a report drawing of the test specimen.



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

TEST REPORT FOR LOFTWALL, INC.


Report No.: R4359.01-113-11-R0

Date: 06/05/24

SECTION 10

TEST RESULTS

ASTM C423 SOUND ABSORPTION TEST



FREQ	REQ EMPTY ROOM		ABSORPTION
	ABSORPTION	ABSORPTION	PER m ²
(Hz)	(m ²)	(m ²)	(SA/m²)
80	5.42	6.66	0.19
100	5.78	7.33	0.23
125	5.66	6.73	0.16
160	4.85	6.69	0.27
200	5.46	8.32	0.43
250	5.54	8.93	0.51
315	5.46	8.10	0.39
400	5.45	7.81	0.35
500	5.05	7.78	0.41
630	4.99	7.84	0.43
800	5.18	8.57	0.51
1000	5.14	9.03	0.58
1250	5.29	10.05	0.71
1600	5.38	10.87	0.82
2000	5.35	11.07	0.86
2500	5.79	12.49	1.00
3150	6.47	13.12	0.99
4000	7.09	14.07	1.04
5000	7.49	14.77	1.09

Array-NRC	0.60	Array-(Noise Reduction Coefficient)
Array-SAA	0.58	Array-(Sound Absorption Average)

Notes:

1) The Array-NRC rating is the arithmetic average of the sound absorption per m^2 at 250, 500, 1000, and 2000 hertz. The average is rounded to the nearest multiple of 0.05.

2) The Array-SAA rating is the arithmetic average of the sound absorption per m^2 at the frequencies ranging from 200 to 2500 hertz. The average is rounded to the nearest multiple of 0.01.



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building


TEST REPORT FOR LOFTWALL, INC.

Report No.: R4359.01-113-11-R0

Date: 06/05/24

ASTM C423 SOUND ABSORPTION TEST

TEST DATE	05/30/24					
DATA FILE NO.	R4359.01D	R4359.01D				
CLIENT	LOFTwall, Inc	4359.01D ACCR OFTwall, Inc.				
DESCRIPTION	Series/Model	: Hedge, Full and	d Low height Storage units			
TECHNICIAN	Zachary P. Go	Zachary P. Golden				
SPECIMEN ARRAY	6.69 m ²	5.69 m²				
MOUNTING TYPE	JV Mod 00	V Mod 00				
	EMPTY	FULL				
TEMP °C	21.0	21.6				
RH %	49	48				
P.D. (mah)	1002	1002	1			





Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

TEST REPORT FOR LOFTWALL, INC.

Report No.: R4359.01-113-11-R0

Date: 06/05/24

SECTION 11

PHOTOGRAPHS



Photo No. 1 View of Installed Test Specimen



Photo No. 2
Side View of Installed Test Specimen



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

TEST REPORT FOR LOFTWALL, INC.

Report No.: R4359.01-113-11-R0

Date: 06/05/24

SECTION 12

REVISION LOG

REVISION #	DATE	PAGES	REVISION
0	06/05/24	N/A	Original Report Issue